

AC MOTOR TEST EQUIPMENTS LIST

EQUIPMENT	CAPACITY/MODEL	Q'TY	Maker	REMARKS
Dynamometer	750KW Dynamometer	1	SCHENCK	LV Motor 7 Line Motor Load test
	700kW Dynamometer	1	SCHENCK	
	100kW Dynamometer	1	API	
	75kW Dynamometer	1	APT	
	30kW Dynamometer	1	SCHENCK	
	250kW AC Dynamometer	1	ABB/HYOSUNG	
	600kW AC Dynamometer	1	ABB/HYOSUNG	
Motor-Generator set	500kVA 0~75Hz , 0~3300V	1	ABB/HYOSUNG	LV Motor Power Line & Loack Rotor test
	1000kVA 0~75HZ, 0~7500V	1	ABB/HYOSUNG	MV / LV Motor No Load Line & Lock Rotor test
	1500kVA 0~75Hz , 0~7500V	1	ABB/HYOSUNG	MV / LV Motor No Load Line Lock Rotor test Temperature rise test
	3500kVA 0~75Hz, 0~7500V	1	ABB/HYOSUNG	MV / LV Motor No Load Line Lock Rotor test Temperature rise test
	6000kVA 0~75Hz , 0~7500V	1	ABB/HYOSUNG	MV / LV Motor No Load Line Lock Rotor test Temperature rise test
Transformer	80000kVA 3Φ 50Hz/60Hz 6.6KV-13.8/11.0/6.6/4.16/3.3KV	1	HYOSUNG	
	60000kVA 3Φ 50Hz/60Hz 6.6KV-13.2/11/6.6/4.16/3.3KV	1	HYOSUNG	
	20000kVA 3Φ 50Hz/60Hz 6.6KV-13.2KV	1	HYOSUNG	
	4000KVA 6.6KV-3.3/2.5/1.5KV	3	HYOSUNG	
	600KVA 6.6KV-3.0/2.5/2.0/1.0/0.5KV	3	HYOSUNG	
	500KVA 6.6KV-2.0/1.5/1.0/0.5KV	3	HYOSUNG	
	2000KVA 6.6KV-3.3KV 430A	1	HYOSUNG	
	25000kVA 3Φ 50Hz/60Hz 6600-690/460/440/415/380V	1	HYOSUNG	
	15000kVA 3Φ 50Hz/60Hz 6600-440/460/440/415/380V	1	HYOSUNG	